



KEYED DEMOLITION NOTES:

1. REMOVE EXISTING STAIR FOUNDATIONS AS NECESSARY FOR NEW CONSTRUCTION ABOVE.
2. REMOVE EXISTING GREENHOUSE FOUNDATION AS NECESSARY FOR NEW CONSTRUCTION ABOVE.
3. REMOVE EXISTING WALL. REF NEW CONSTRUCTION PLANS FOR SPECIFIC RENOVATION WORK REQUIREMENTS.
4. REMOVE EXISTING GREENHOUSE.
5. REMOVE EXIST BRICK AND STONWORK AS REQUIRED TO ALLOW FOR NEW OPENING. SALVAGE EXIST BRICK AND STONE FOR REUSE IN NEW CONSTRUCTION. REBUILD MASONRY BRICK AND STONWORK OPENINGS TO BE TOOTHED-IN. TYP.
6. REMOVE ALL EXISTING HARDSCAPE. REF NEW CONSTRUCTION PLANS FOR SPECIFIC RENOVATION WORK REQUIREMENTS.
7. APPROXIMATE AREA OF EXCAVATION. REF NEW CONSTRUCTION PLANS FOR SPECIFIC NEW WORK REQUIREMENTS.
8. REMOVE EXISTING WINDOW AND MASONRY BELOW. SALVAGE EXIST BRICK AND STONE FOR REUSE IN NEW CONSTRUCTION. PREP MASONRY OPENING TO ALLOW FOR NEW DOOR. REF NEW WORK DRAWINGS. TYP.
9. REMOVE EXIST DOOR. PREP MASONRY OPENING TO ALLOW FOR NEW WINDOW. REF NEW WORK DRAWINGS. TYP.
10. APPROXIMATE AREA OF EXISTING FLOOR TO BE REMOVED. REF NEW CONSTRUCTION PLANS FOR SPECIFIC RENOVATION WORK REQUIREMENTS.
11. REMOVE EXISTING INTERIOR DOOR AND DOOR FRAME. SALVAGE FOR OWNER'S USE. STORE ON-SITE AS DIRECTED. PREP WALL OPENING TO RECEIVE NEW DOOR AND FRAME.
12. REMOVE EXISTING DOOR. PREP MASONRY OPENING TO ALLOW FOR NEW DOOR. REF NEW WORK DRAWINGS. TYP.
13. REMOVE EXISTING STAIR TO ALLOW FOR NEW WORK. REF NEW WORK DRAWINGS. TYP.
14. NOT USED.
15. REMOVE EXISTING WINDOW AND BRICK AS REQUIRED TO ALLOW FOR NEW OPENING. SALVAGE EXIST BRICK FOR REUSE IN NEW CONSTRUCTION. REBUILD MASONRY BRICK OPENINGS TO BE TOOTHED-IN. TYP.
16. REMOVE EXIST INTERIOR WALL AS NECESSARY FOR NEW WORK. REBUILD MASONRY BRICK OPENINGS TO BE TOOTHED-IN. TYP.
17. REMOVE EXISTING WINDOW AND FRAME. PREP WALL OPENING TO RECEIVE NEW WINDOW AND FRAME.
18. REMOVE EXISTING DOOR. REBUILD MASONRY BRICK AND STONWORK OPENING TO BE TOOTHED-IN. TYP.
19. REMOVE EXISTING WINDOW AND MASONRY AS REQUIRED FOR NEW WORK. SALVAGE EXIST BRICK AND STONE FOR REUSE IN NEW CONSTRUCTION. PREP MASONRY OPENING TO ALLOW FOR NEW LARGER WINDOW. REF NEW WORK DRAWINGS. TYP.
20. REMOVE EXISTING WINDOW AS REQUIRED TO ALLOW FOR NEW WORK. PREP MASONRY OPENING TO ALLOW FOR MASONRY INFILL. REF. NEW WORK DRAWINGS. TYP.
21. REMOVE EXISTING STAIRS AND RAILINGS. SALVAGE STONE AND RAILINGS FOR USE IN NEW CONSTRUCTION.
22. PATCH, REPAIR AND REPLACE DAMAGED ROOFING SLATES.

LEGEND

- LIMITS OF WORK
- WALL OR EQUIPMENT TO BE REMOVED U.O.N.
- PROPERTY LINE
- EXISTING TO REMAIN
- DEFINED AREA OF DEMOLITION
- LINE OF ROOF ABOVE

EXTENT OF DEMOLITION SHOWN AND DIMENSIONS PROVIDED ARE APPROXIMATE. CONTRACTOR TO REVIEW FIELD CONDITIONS AND COORDINATE DEMOLITION WORK WITH NEW CONSTRUCTION PLANS, INCLUDING ARCHITECTURAL, CIVIL, STRUCTURAL, MECHANICAL, ELECTRICAL AND PLUMBING.

1 DEMO FIRST FLOOR PLAN
SCALE: 1/8" = 1'-0"

CLIENT



WOODROW WILSON HIGH SCHOOL

3950 Chesapeake St NW
Washington, DC 20016
T: 202-282-0120

ARCHITECT



cox graeo + spack architects

2909 M STREET NW,
WASHINGTON, DC 20007
T: 202-965-7070 F: 202-965-7144

ASSOCIATE ARCHITECTS

Fanning - Howey

210 North Lee Street, Suite 208
Alexandria, VA 22314
T: 703.519.9822 F: 703.519.9823

CONSULTANTS

CIVIL ENGINEERING

Delon Hampton & Associates
8403 Colesville Rd, Suite 600
Silver Spring, MD 20910
T: 301.585.0100 F: 301.585.6486

GEOTECHNICAL ENGINEERING

Thomas L. Brown Associates

1400 Eye Street NW, Suite 440
Washington, DC 20005
T: 202.387.0022 F: 202.682.1367

MEP ENGINEERING

Fanning - Howey

210 North Lee Street, Suite 208
Alexandria, VA 22314
T: 703.519.9822 F: 703.519.9823

STRUCTURAL ENGINEERING

ReStl Designers, INC.

702 Russel Avenue, Suite 400
Gaithersburg, MD 20877
T: 301.257.6872 F: 301.926.3109

REGISTRATION

MARK	DATE	DESCRIPTION
	09.25.2009	Schematic Design Submittal

CGS PROJECT NO.: 2905

DRAWN BY:

CHECKED BY:

GRAPHIC SCALE:

KEY PLAN

SHEET TITLE

DEMO CORRIDORS "A" AND "B"
- FIRST FLOOR PLAN

AD2.07